

**CITY OF ELK GROVE  
CONSTRUCTION SPECIFICATIONS  
TABLE OF CONTENTS**

**SECTION 1 - TERMS AND DEFINITIONS**

|     |                    |   |
|-----|--------------------|---|
| 1-1 | GENERAL .....      | 1 |
| 1-2 | ABBREVIATIONS..... | 1 |
| 1-3 | DEFINITIONS .....  | 3 |

**SECTION 2 - BID REQUIREMENTS AND CONDITIONS**

|      |  |    |
|------|--|----|
| 2-1  | BID FORM .....   | 9  |
|      | 2-1.01    UNIT PRICE BID.....                                    | 9  |
|      | 2-1.02    LUMP SUM BID.....                                      | 9  |
|      | 2-1.03    ALLOWANCES.....  | 9  |
| 2-2  | PREPARATION AND SUBMISSION OF BIDS.....                          | 10 |
| 2-3  | EXAMINATIONS OF PLANS, SPECIFICATIONS, AND SITE<br>OF WORK ..... | 10 |
| 2-4  | SUBSURFACE CONDITIONS.....                                       | 11 |
| 2-5  | CONTRACTORS/SUBCONTRACTORS REQUIRED TO BE<br>LICENSED .....      | 11 |
| 2-6  | COMPETENCY OF BIDDERS.....                                       | 11 |
| 2-7  | JOINT VENTURE BIDS.....  | 12 |
| 2-8  | SUBCONTRACTORS .....   | 12 |
| 2-9  | ADDENDA .....  | 13 |
| 2-10 | ASSIGNMENT OF ANTITRUST ACTIONS .....                            | 13 |
| 2-11 | BID GUARANTEE.....   | 13 |
| 2-12 | WITHDRAWAL OF BID.....   | 13 |
| 2-13 | PUBLIC OPENING OF BIDS .....                                     | 13 |
| 2-14 | REJECTION OF BIDS .....  | 14 |
| 2-15 | RELIEF OF BIDDERS.....   | 14 |

**SECTION 3 - AWARD AND EXECUTION OF CONTRACT**

|     |                                       |    |
|-----|---------------------------------------|----|
| 3-1 | AWARD OF CONTRACT.....                | 15 |
| 3-2 | TIME OF AWARD.....                    | 15 |
| 3-3 | CONSIDERATION OF BIDS.....            | 15 |
| 3-4 | PERFORMANCE AND PAYMENT BONDS.....    | 15 |
|     | 3-4.01    PERFORMANCE BOND .....      | 16 |
|     | 3-4.02    PAYMENT BOND .....          | 16 |
| 3-5 | NOTIFICATION OF SURETY COMPANIES..... | 16 |
| 3-6 | RETURN OF BID GUARANTEES .....        | 16 |
| 3-7 | EXECUTION OF CONTRACT.....            | 16 |
| 3-8 | FAILURE TO EXECUTE CONTRACT.....      | 17 |
| 3-9 | INSURANCE .....                       | 17 |
|     | 3-9.01    GENERAL LIABILITY .....     | 17 |
|     | 3-9.02    AUTOMOBILE LIABILITY.....   | 18 |

|          |   |    |
|----------|---|----|
| 3-9.03   | WORKERS' COMPENSATION.....                  | 18 |
| 3-9.04   | EXCESS OR UMBRELLA LIABILITY .....          | 18 |
| 3-9.04.A | CONTRACTOR'S EQUIPMENT.....                 | 18 |
| 3-9.04.B | RAILROAD PROTECTIVE LIABILITY .....         | 18 |
| 3-9.04.C | BUILDER'S RISK INSURANCE .....              | 19 |
| 3-9.04.D | ENVIRONMENTAL LIABILITY INSURANCE .....     | 20 |
| 3-9.04.E | OTHER PROVISIONS.....                       | 20 |
| 3-9.05   | NOTIFICATION OF ACCIDENT OR OCCURRENCE..... | 22 |

#### **SECTION 4 -SCOPE OF WORK**

|        |  |    |
|--------|--|----|
| 4-1    | INTENT OF CONTRACT DOCUMENTS.....                    | 23 |
| 4-2    | PLANS AND SPECIFICATIONS FURNISHED .....             | 23 |
| 4-3    | CONFORMANCE WITH CODES AND STANDARDS.....            | 24 |
| 4-4    | SUPPLEMENTAL DRAWINGS.....                           | 24 |
| 4-5    | FIELD INSTRUCTIONS OR OTHER WRITTEN DIRECTIVES ..... | 24 |
| 4-6    | DOCUMENT PRECEDENCE.....                             | 25 |
| 4-7    | REQUESTS FOR INFORMATION .....                       | 25 |
| 4-7.01 | GENERAL .....  | 25 |
| 4-7.02 | PROCEDURE .....                                      | 25 |
| 4-7.03 | RESPONSE.....  | 26 |
| 4-8    | DELETED ITEMS.....                                   | 26 |
| 4-9    | EXTRA WORK .....                                     | 26 |
| 4-10   | USE OF COMPLETED PORTIONS.....                       | 26 |
| 4-11   | LANDS AND RIGHTS-OF-WAY.....                         | 27 |
| 4-12   | WARRANTY .....                                       | 27 |

#### **SECTION 5 - CONTROL OF WORK AND MATERIALS**

|        |   |    |
|--------|---|----|
| 5-1    | AUTHORITY OF CITY.....  | 28 |
| 5-2    | ATTENTION AND COOPERATION OF CONTRACTOR .....                           | 28 |
| 5-3    | SUGGESTIONS TO CONTRACTOR .....   | 28 |
| 5-4    | SEPARATE CONTRACTS .....  | 28 |
| 5-5    | COOPERATION WITH OTHER CONTRACTORS.....                                 | 28 |
| 5-6    | CONTRACTOR'S DISMISSAL OF UNSATISFACTORY<br>EMPLOYEES.....              | 29 |
| 5-7    | CONTRACTOR'S EQUIPMENT.....   | 29 |
| 5-8    | CONTRACTOR'S SUBMITTALS.....  | 29 |
| 5-8.01 | SUBMITTALS - GENERAL.....   | 29 |
| 5-8.02 | RESUBMITTALS.....   | 30 |
| 5-8.03 | SUBMITTALS CONTAINING PROPRIETARY<br>INFORMATION.....                   | 30 |
| 5-8.04 | ELECTRICAL, INSTRUMENTATION, CONTROL,<br>AND COMMUNICATION SYSTEMS..... | 31 |
| 5-8.05 | MAINTENANCE AND OPERATIONS (M&O)<br>SUBMITTALS.....                     | 31 |
| 5-9    | SURVEYS .....   | 32 |
| 5-9.02 | STREETS AND HIGHWAYS.....   | 32 |
| 5-9.03 | SEWER, WATER, AND DRAINAGE FACILITIES.....                              | 33 |
| 5-9.04 | SURVEY MONUMENTS.....   | 33 |
| 5-10   | RESPONSIBILITY FOR ACCURACY.....  | 33 |
| 5-11   | DUTIES AND POWERS OF INSPECTORS.....                                    | 33 |
| 5-12   | INSPECTION .....  | 34 |

|           |   |    |
|-----------|---|----|
| 5-13      | QUALITY OF MATERIALS AND WORKMANSHIP .....                  | 34 |
| 5-14      | SUBSTITUTIONS.....  | 34 |
| 5-14.01   | WRITTEN REQUEST .....                                       | 35 |
| 5-14.02   | DOCUMENTATION .....   | 35 |
| 5-15      | PREPARATION FOR TESTING.....                                | 35 |
| 5-16      | MATERIALS SAMPLING AND TESTING.....                         | 35 |
| 5-17      | APPROVAL OF MATERIALS .....                                 | 36 |
| 5-17.01   | SOURCES OF SUPPLY .....                                     | 36 |
| 5-17.02   | PLANT INSPECTION .....                                      | 36 |
| 5-18      | PROVISIONS FOR EMERGENCIES .....                            | 36 |
| 5-19      | RIGHT TO RETAIN IMPERFECT WORK.....                         | 37 |
| 5-20      | REMOVAL OF REJECTED MATERIALS OR WORK .....                 | 37 |
| 5-21      | TEMPORARY SUSPENSION OR DELAY OF WORK.....                  | 37 |
| 5-22      | TERMINATION OF CONTRACT.....                                | 37 |
| 5-22.01   | REASONS FOR TERMINATION .....                               | 37 |
| 5-22.01.A | CONTRACTOR BANKRUPT .....                                   | 37 |
| 5-22.01.B | COMPLETION DELAY.....                                       | 38 |
| 5-22.01.C | ABANDONMENT AND UNSATISFACTORY<br>PERFORMANCE .....         | 38 |
| 5-22.01.D | TERMINATION OF CONTRACT FOR<br>CONVENIENCE .....            | 38 |
| 5-22.02   | NOTICE OF TERMINATION .....                                 | 38 |
| 5-22.03   | PAYMENTS TO CONTRACTOR UPON<br>TERMINATION OF CONTRACT..... | 39 |
| 5-22.04   | CITY COMPLETION .....                                       | 40 |
| 5-22.04.A | PAYMENT FOR CITY COMPLETION.....                            | 40 |
| 5-22.04.B | CITY COMPLETION NOT A WAIVER OF CITY<br>RIGHTS.....         | 41 |
| 5-23      | TERMINATION OF UNSATISFACTORY SUBCONTRACTS .....            | 41 |

## **SECTION 6 – LEGAL RELATIONS AND RESPONSIBILITIES**

|        |  |    |
|--------|--|----|
| 6-1    | COMPLIANCE WITH LAWS AND REGULATIONS .....             | 42 |
| 6-1.01 | HOURS OF LABOR.....                                    | 42 |
| 6-1.02 | PREVAILING WAGE .....                                  | 42 |
| 6-1.03 | PAYROLL RECORDS.....                                   | 43 |
| 6-1.04 | NONDISCRIMINATION .....                                | 43 |
| 6-1.05 | APPRENTICES.....                                       | 43 |
| 6-1.06 | WORKERS' COMPENSATION.....                             | 44 |
| 6-1.07 | FAIR LABOR STANDARDS .....                             | 44 |
| 6-1.08 | CONTRACTORS LICENSE .....                              | 44 |
| 6-1.09 | USE OF PESTICIDES.....                                 | 44 |
| 6-1.10 | REPORTING REQUIREMENTS AND SANCTIONS.....              | 44 |
| 6-1.11 | SUBCONTRACTING .....                                   | 45 |
| 6-1.12 | OCCUPATIONAL SAFETY AND HEALTH.....                    | 45 |
| 6-2    | INDEMNIFICATION.....                                   | 45 |
| 6-2.01 | CONTRACTOR'S PERFORMANCE.....                          | 45 |
| 6-2.02 | NO LIMITATION OF LIABILITY FOR<br>INDEMNIFICATION..... | 46 |
| 6-3    | CONTRACTOR'S LEGAL ADDRESS.....                        | 46 |
| 6-4    | CONTRACTOR NOT AN AGENT OF CITY .....                  | 46 |
| 6-5    | SUBSTITUTION OF SUBCONTRACTORS.....                    | 46 |
| 6-6    | ASSIGNMENT OF CONTRACT .....                           | 47 |

|         |  |    |
|---------|--|----|
| 6-7     | ASSIGNMENT OF MONIES .....   | 47 |
| 6-8     | PROTECTION OF CITY AGAINST PATENT CLAIMS .....                                 | 47 |
| 6-9     | RESPONSIBILITY OF THE CONTRACTOR .....   | 47 |
| 6-10    | PERMITS AND LICENSES .....   | 48 |
| 6-11    | GENERAL SAFETY REQUIREMENTS .....  | 48 |
| 6-11.01 | COMPLIANCE WITH SAFETY & HEALTH REGULATIONS.....                               | 48 |
| 6-11.02 | 24-HOUR CONTACT INFORMATION .....  | 49 |
| 6-11.03 | WORK DURING HOURS OF DARKNESS.....   | 49 |
| 6-12    | PUBLIC CONVENIENCE AND SAFETY.....   | 49 |
| 6-12.01 | PUBLIC CONVENIENCE.....  | 49 |
| 6-12.02 | PEDESTRIAN AND BICYCLIST ACCESS .....  | 49 |
| 6-12.03 | WRITTEN NOTIFICATION TO RESIDENCES AND BUSINESSES.....                         | 50 |
| 6-12.04 | ACCESS TO DRIVEWAYS, HOUSES AND BUILDINGS .....                                | 50 |
| 6-12.05 | PROPERTY DAMAGE.....   | 50 |
| 6-12.06 | ERECTION OF SIGNS TO EXPEDITE PASSAGE OF VEHICLES.....                         | 50 |
| 6-12.07 | TRAFFIC OBSTRUCTIONS, DELAYS AND INCONVENIENCES.....                           | 51 |
| 6-12.08 | WORK ON PRIVATE PROPERTY .....   | 51 |
| 6-12.09 | HAZARDOUS CONDITIONS CREATED .....   | 51 |
| 6-13    | PUBLIC SAFETY AND TRAFFIC CONTROL.....   | 51 |
| 6-13.01 | GENERAL .....  | 51 |
| 6-13.02 | RESPONSIBILITY FOR SAFETY .....  | 51 |
| 6-13.03 | PASSAGE OF EMERGENCY VEHICLES.....   | 51 |
| 6-13.04 | FURNISHING, INSTALLING, AND MAINTAINING TRAFFIC CONTROLS .....                 | 52 |
| 6-13.05 | INADEQUATE TRAFFIC CONTROLS AND AFTER-HOUR MAINTENANCE AND REPAIRS.....        | 52 |
| 6-13.06 | COMPETENT FLAGGERS .....   | 52 |
| 6-13.07 | CONSTRUCTION SIGNS.....  | 52 |
| 6-13.08 | TEMPORARY BRIDGING OF EXCAVATIONS AND TRENCHES.....                            | 53 |
| 6-13.09 | ENTERING AND LEAVING THE CONSTRUCTION ZONE .....                               | 53 |
| 6-13.10 | EXISTING TRAFFIC SIGNAL AND LIGHTING SYSTEMS, SIGNS AND PAVEMENT MARKINGS..... | 54 |
| 6-13.11 | BUS STOPS.....   | 54 |
| 6-13.12 | DUST.....  | 54 |
| 6-13.13 | REMOVAL OF SPILLAGE FROM ROADWAY .....   | 54 |
| 6-14    | TRAFFIC CONTROL PLANS (TCP).....   | 54 |
| 6-14.01 | TRAFFIC PATTERN CHANGES.....   | 54 |
| 6-14.02 | TRAFFIC CONTROL PLANS (TCP).....   | 55 |
| 6-15    | BARRICADING OPEN TRENCHES.....   | 55 |
| 6-16    | EXISTING UTILITIES.....  | 55 |
| 6-16.01 | GENERAL .....  | 55 |
| 6-16.02 | MAINTENANCE AND PROTECTION.....  | 55 |
| 6-16.03 | EXACT LOCATIONS UNKNOWN.....   | 56 |
| 6-16.04 | UNDERGROUND SERVICE ALERT (USA).....   | 56 |
| 6-16.05 | DAMAGE TO EXISTING UTILITIES.....  | 57 |
| 6-16.06 | MARKINGS.....  | 57 |

|         |  |    |
|---------|--|----|
| 6-17    | APPROVAL OF CONTRACTOR'S PLANS NO RELEASE FROM LIABILITY ..... | 58 |
| 6-18    | CONTRACTOR SHALL NOT MORTGAGE EQUIPMENT.....                   | 58 |
| 6-19    | PROPERTY RIGHTS IN MATERIALS.....                              | 58 |
| 6-20    | EXCAVATION AND TRENCH SAFETY.....                              | 58 |
| 6-20.01 | PERMIT .....   | 58 |
| 6-20.02 | SHORING, BRACING, SHIELDING AND SHEETING.....                  | 58 |
| 6-21    | PRESERVATION OF PROPERTY.....                                  | 59 |
| 6-22    | OVERLOADING.....   | 59 |

## **SECTION 7 - PROSECUTION OF THE WORK**

|         |  |    |
|---------|--|----|
| 7-1     | BEGINNING OF WORK.....   | 60 |
| 7-2     | AMOUNT OF WORK UNDER CONSTRUCTION.....   | 60 |
| 7-3     | PRECONSTRUCTION CONFERENCE AND PROGRESS MEETINGS.....                                    | 60 |
| 7-4     | WORK TO BE PROSECUTED WITH ADEQUATE SUPERVISION, LABOR FORCE, EQUIPMENT AND METHODS..... | 60 |
| 7-4.01  | SUPERINTENDENCE .....  | 60 |
| 7-4.02  | LABOR .....  | 61 |
| 7-4.03  | EQUIPMENT AND METHODS.....   | 61 |
| 7-5     | SCHEDULES .....  | 61 |
| 7-5.01  | PROGRESS SCHEDULE.....   | 61 |
| 7-5.02  | CPM SCHEDULE .....   | 62 |
| 7-5.03  | THREE-WEEK ROLLING SCHEDULE .....  | 63 |
| 7-6     | UNUSUAL SITE CONDITIONS.....   | 63 |
| 7-7     | PURSUANCE OF WORK DURING INCLEMENT WEATHER .....   | 63 |
| 7-8     | PEAK HOURS, HOURS OF DARKNESS, HOLIDAYS, AND WEEKENDS.....                               | 64 |
| 7-8.01  | ALLOWABLE TIMES AND HOURS OF WORK .....  | 64 |
| 7-8.02  | OFF-PERIOD WORK.....   | 64 |
| 7-8.03  | EMERGENCY REPAIRS .....  | 64 |
| 7-8.04  | REVOCATION OF PERMISSION FOR OFF-PERIOD WORK .....                                       | 64 |
| 7-8.05  | WORKING SHIFTS.....  | 64 |
| 7-8.06  | LANE AND ROAD CLOSURES DURING NOVEMBER/DECEMBER HOLIDAY SEASON .....                     | 65 |
| 7-9     | TEMPORARY FACILITIES AND SERVICES .....  | 65 |
| 7-10    | PROTECTION OF WORK, PERSONS AND PROPERTY.....  | 65 |
| 7-11    | PROOF OF COMPLIANCE WITH CONTRACT .....  | 65 |
| 7-12    | DELAYS.....  | 65 |
| 7-12.01 | AVOIDABLE DELAYS.....  | 65 |
| 7-12.02 | UNAVOIDABLE DELAYS .....   | 66 |
| 7-13    | NOTICE OF DELAYS .....   | 66 |
| 7-14    | CARELESS DESTRUCTION OF STAKES AND MARKS NO CAUSE FOR DELAY.....                         | 67 |
| 7-15    | TIME OF COMPLETION.....  | 67 |
| 7-16    | EXTENSION OF TIME NOT A WAIVER.....  | 67 |
| 7-17    | INCLEMENT WEATHER AND CONTRACT TIME.....   | 67 |
| 7-18    | EXTENSION OF TIME .....  | 67 |
| 7-19    | SUBSTANTIAL COMPLETION.....  | 68 |
| 7-20    | CLEANING UP .....  | 68 |

|      |   |    |
|------|---|----|
| 7-21 | FINAL INSPECTION AND FIELD ACCEPTANCE.....      | 68 |
| 7-22 | FINAL ACCEPTANCE AND NOTICE OF COMPLETION ..... | 69 |
| 7-23 | RELEASE OF WARRANTY PERIOD .....                | 69 |

**SECTION 8 – MEASUREMENT AND PAYMENT**

|          |  |    |
|----------|--|----|
| 8-1      | BASIS AND MEASUREMENT OF PAYMENT QUANTITIES.....                             | 70 |
| 8-1.01   | UNIT PRICE CONTRACTS.....  | 70 |
| 8-1.02   | LUMP SUM OR JOB CONTRACTS .....  | 70 |
| 8-1.03   | PAYMENT FOR MOBILIZATION.....  | 70 |
| 8-1.03.A | MOBILIZATION NOT A PAY ITEM.....   | 70 |
| 8-1.03.B | MOBILIZATION A PAY ITEM .....  | 70 |
| 8-2      | SCOPE OF PAYMENT .....   | 71 |
| 8-2.01   | GENERAL .....  | 71 |
| 8-2.02   | UNIT PRICE CONTRACT .....  | 71 |
| 8-2.03   | LUMP SUM OR JOB CONTRACT.....  | 72 |
| 8-2.04   | FINAL PAY ITEMS.....   | 72 |
| 8-2.05   | ALLOWANCES.....  | 72 |
| 8-2.06   | PAYMENT FOR MATERIAL NOT INCORPORATED<br>IN THE WORK.....                    | 72 |
| 8-3      | WORK TO BE DONE WITHOUT DIRECT PAYMENT .....                                 | 72 |
| 8-4      | PAYMENT FOR USE OF COMPLETED PORTIONS OF WORK .....                          | 72 |
| 8-5      | PROGRESS PAYMENT PROCEDURES .....  | 73 |
| 8-6      | INSPECTION AND PROGRESS PAYMENTS NOT A WAIVER<br>OF CONTRACT PROVISIONS..... | 73 |
| 8-7      | RETENTION .....  | 73 |
| 8-7.01   | RETENTION TO ENSURE PERFORMANCE .....  | 73 |
| 8-7.02   | NON-COMPLIANCE .....   | 73 |
| 8-7.03   | SUBSTITUTION OF SECURITIES.....  | 73 |
| 8-8      | WITHHOLDINGS/DENIAL OF PROGRESS PAYMENT<br>REQUEST.....                      | 74 |
| 8-9      | DEDUCTIONS FOR IMPERFECT WORK.....   | 75 |
| 8-10     | LIQUIDATED DAMAGES FOR DELAY .....   | 75 |
| 8-11     | FINAL ESTIMATE AND PAYMENT.....  | 75 |
| 8-12     | FINAL PAYMENT TO TERMINATE LIABILITY OF CITY OF<br>ELK GROVE .....           | 75 |
| 8-13     | DISPUTED PAYMENTS .....  | 76 |

**SECTION 9 – CHANGES AND CLAIMS**

|        |   |    |
|--------|---|----|
| 9-1    | AUTHORITY FOR CHANGES.....                          | 77 |
| 9-2    | ORDERING OF CHANGES .....                           | 77 |
| 9-3    | CONSTRUCTION INCENTIVE CHANGE PROPOSAL (CICP) ..... | 77 |
| 9-3.01 | GENERAL .....                                       | 77 |
| 9-3.02 | DESCRIPTION .....                                   | 77 |
| 9-3.03 | SUBMITTAL .....                                     | 78 |
| 9-3.04 | ACCEPTANCE.....                                     | 79 |
| 9-3.05 | SHARING PROVISIONS AND FORMULA.....                 | 79 |
| 9-4    | CHANGES TO THE CONTRACT .....                       | 79 |
| 9-5    | PROSECUTION OF CHANGES TO THE CONTRACT .....        | 80 |
| 9-6    | COST AND PRICING DATA.....                          | 80 |
| 9-7    | ACCESS TO RECORDS.....                              | 80 |
| 9-8    | PAYMENT FOR CHANGES.....                            | 80 |

|              |   |    |
|--------------|---|----|
| 9-8.01       | LUMP SUM PRICE .....  | 80 |
| 9-8.02       | UNIT PRICES .....   | 81 |
| 9-8.03       | FORCE ACCOUNT .....   | 81 |
| 9-8.03.A     | LABOR .....   | 81 |
| 9-8.03.A.(1) | ACTUAL WAGES .....  | 81 |
| 9-8.03.A.(2) | LABOR SURCHARGE .....   | 81 |
| 9-8.03.A.(3) | SUBSISTENCE AND TRAVEL .....  | 82 |
| 9-8.03.B     | MATERIALS.....  | 82 |
| 9-8.03.C     | EQUIPMENT .....   | 82 |
| 9-8.03.D     | SUBCONTRACTS.....   | 82 |
| 9-9          | MARKUPS FOR CHANGED WORK.....   | 82 |
| 9-10         | COMPENSABLE UNAVOIDABLE DELAYS.....                                   | 83 |
| 9-10.01      | CONSTRUCTION EQUIPMENT.....   | 83 |
| 9-10.02      | JOBSITE INDIRECT COSTS.....   | 83 |
| 9-10.03      | MARKUP FOR COMPENSABLE UNAVOIDABLE<br>DELAYS .....                    | 84 |
| 9-10.04      | DUPLICATED OVERHEAD COSTS.....  | 84 |
| 9-11         | LIMITATIONS ON PAYMENTS FOR CHANGED WORK.....                         | 84 |
| 9-12         | TIME EXTENSIONS FOR CHANGES .....                                     | 84 |
| 9-13         | EFFECT ON SURETIES OF CHANGES TO THE WORK.....                        | 84 |
| 9-14         | CONTRACT CHANGE ORDER (CCO).....                                      | 84 |
| 9-15         | ACCEPTANCE OF ORDERS FOR CHANGES .....                                | 85 |
| 9-16         | DISPUTE REGARDING CONTRACT REQUIREMENTS.....                          | 85 |
| 9-17         | NOTICE OF POTENTIAL CLAIM .....                                       | 85 |
| 9-18         | RESOLUTION OF CLAIMS.....   | 86 |
| 9-18.01      | CONTRACTOR'S DUTY DURING CLAIM<br>RESOLUTION.....                     | 87 |
| 9-19         | ENGINEER'S DECISION .....   | 87 |
| 9-20         | ALTERNATIVE DISPUTE RESOLUTION .....                                  | 88 |
| 9-20.01      | INITIATION OF MEDIATION.....  | 88 |
| 9-20.02      | REQUEST FOR MEDIATION .....   | 88 |
| 9-20.03      | SELECTION OF MEDIATOR.....  | 88 |
| 9-20.04      | QUALIFICATIONS OF A MEDIATOR.....                                     | 88 |
| 9-20.05      | VACANCIES .....   | 88 |
| 9-20.06      | REPRESENTATION.....   | 89 |
| 9-20.07      | TIME AND PLACE OF MEDIATION .....                                     | 89 |
| 9-20.08      | IDENTIFICATION OF MATTERS IN DISPUTE .....                            | 89 |
| 9-20.09      | AUTHORITY OF MEDIATOR.....  | 89 |
| 9-20.10      | PRIVACY .....   | 89 |
| 9-20.11      | CONFIDENTIALITY .....   | 89 |
| 9-20.12      | NO STENOGRAPHIC RECORD .....  | 90 |
| 9-20.13      | TERMINATION OF MEDIATION.....   | 90 |
| 9-20.14      | EXCLUSION OF LIABILITY.....   | 90 |
| 9-20.15      | INTERPRETATION AND APPLICATION OF THESE<br>MEDIATION PROVISIONS ..... | 90 |
| 9-20.16      | EXPENSES.....   | 90 |
| 9-21         | NO ALTERNATIVE CLAIMS PROCEDURE.....                                  | 90 |
| 9-22         | ASSIGNMENT OF CLAIMS .....  | 90 |

**SECTION 10 – ENVIRONMENTAL CONTROLS AT WORK SITE**

|      |                            |    |
|------|----------------------------|----|
| 10-1 | DUST CONTROL.....          | 91 |
| 10-2 | AIR POLLUTION CONTROL..... | 91 |

|          |   |    |
|----------|---|----|
| 10-3     | BURNING.....  | 91 |
| 10-4     | EROSION, SEDIMENT, AND WATER POLLUTION CONTROL .....      | 91 |
| 10-4.01  | GENERAL .....   | 91 |
| 10-4.02  | CITY REQUIREMENTS.....                                    | 91 |
| 10-4.03  | REGULATIONS, ORDINANCES, PERMITS, AND SPECIFICATIONS..... | 92 |
| 10-4.04  | STORMWATER POLLUTION PREVENTION PLAN .....                | 92 |
| 10-4.05  | EROSION AND SEDIMENT CONTROL PLAN .....                   | 94 |
| 10-4.06  | MINIMUM CITY REQUIREMENTS.....                            | 94 |
| 10-4.07  | COMPLIANCE.....   | 95 |
| 10-4.08  | PAYMENT .....   | 95 |
| 10-5     | CONTROL OF WATER IN THE WORK.....                         | 95 |
| 10-6     | NOISE CONTROL .....                                       | 96 |
| 10-7     | CONTAMINATED AND HAZARDOUS MATERIALS OR ENVIRONMENTS..... | 96 |
| 10-7.01  | CONTAMINATED OR HAZARDOUS MATERIALS.....                  | 96 |
| 10-7.02  | HAZARDOUS ENVIRONMENTS.....                               | 96 |
| 10-8     | USE OF EXPLOSIVES.....                                    | 96 |
| 10-9     | SANITARY REGULATIONS.....                                 | 96 |
| 10-10    | CONFINED SPACES .....                                     | 97 |
| 10-10.01 | CONTRACTOR RESPONSIBILITIES AND QUALIFICATIONS.....       | 97 |
| 10-10.02 | CITY RESPONSIBILITIES FOR PERMIT CONFINED SPACES.....     | 97 |
| 10-10.03 | EXISTING SEWERS AND STORM DRAINS .....                    | 98 |
| 10-10.04 | JOINT CITY - CONTRACTOR ENTRIES .....                     | 98 |
| 10-11    | CLEANING UP .....   | 98 |
| 10-12    | ARCHEOLOGICAL AND CULTURAL RESOURCES .....                | 98 |
| 10-13    | PROTECTION OF EXISTING TREES.....                         | 99 |

## **SECTION 11 – RECORD DRAWINGS**

|      |                                    |     |
|------|------------------------------------|-----|
| 11-1 | GENERAL .....                      | 100 |
| 11-2 | RESERVED.....                      | 100 |
| 11-3 | AS BUILT DRAWINGS (AS BUILTS)..... | 100 |

## **SECTION 12 – CONSTRUCTION AREA TRAFFIC CONTROL**

|               |   |     |
|---------------|---|-----|
| 12-1          | GENERAL .....                               | 101 |
| 12-2          | FLAGGING.....                               | 101 |
| 12-2.01       | FLAGGERS .....                              | 101 |
| 12-2.02       | FLAGGING COSTS.....                         | 101 |
| 12-3          | TRAFFIC-HANDLING EQUIPMENT AND DEVICES..... | 102 |
| 12-3.01       | GENERAL .....                               | 102 |
| 12-3.02       | CONES.....                                  | 102 |
| 12-3.03       | PORTABLE CHANNELIZERS.....                  | 102 |
| 12-3.04       | TELESCOPING FLAG TREES.....                 | 103 |
| 12-3.05       | PORTABLE FLASHING BARRICADES .....          | 103 |
| 12-3.06       | BARRICADES.....                             | 103 |
| 12-3.06.A     | MATERIALS.....                              | 103 |
| 12-3.06.B     | INSTALLATION AND MAINTENANCE.....           | 104 |
| 12-3.06.B.(1) | CONSTRUCTION BARRICADES.....                | 104 |
| 12-3.06.B.(2) | PERMANENT BARRICADES.....                   | 104 |



|           |   |     |
|-----------|---|-----|
| 12-3.07   | FLASHING ARROW SIGN (FAS).....  | 104 |
| 12-3.08   | CONSTRUCTION AREA SIGNS.....  | 105 |
| 12-3.08.A | GENERAL REQUIREMENTS .....  | 105 |
| 12-3.08.B | COVERING SIGNS .....  | 105 |
| 12-3.08.C | CLEANING SIGNS .....  | 105 |
| 12-3.08.D | USED SIGNS.....   | 105 |
| 12-3.08.E | REPLACEMENT AND BACKUP SIGNS.....   | 105 |
| 12-3.08.F | STOPPING OR PARKING PROHIBITION (TOW-<br>AWAY ZONE).....                        | 106 |
| 12-3.08.G | PROTECTION, MAINTENANCE, REMOVAL,<br>STORAGE, AND RESETTING OF SIGNS .....      | 106 |
| 12-3.08.H | MOVEMENT OF TRAFFIC SIGNS AND TRAFFIC<br>CONTROL FACILITIES .....               | 106 |
| 12-3.08.I | “ROAD CONSTRUCTION AHEAD (C-18)” AND<br>“END OF CONSTRUCTION (C-13)” SIGNS..... | 106 |
| 12-3.08.J | CONTRACTOR FURNISHED SIGNS .....  | 106 |
| 12-3.08.K | OBSCURING VISIBILITY AND CONFLICTING WITH<br>MEANING.....                       | 106 |
| 12-3.08.L | PERMANENT CONSTRUCTION SIGNS .....  | 107 |
| 12-3.08.M | REMOVAL OF PERMANENT TRAFFIC CONTROL<br>SIGNS.....                              | 107 |
| 12-3.08.N | REGULATORY SIGN PLACEMENT AND REMOVAL.....                                      | 107 |
| 12-3.08.O | SIGN POSTS.....   | 108 |
| 12-4      | MEASUREMENT AND PAYMENT .....   | 108 |

### **SECTION 13 –EXISTING FACILITIES**

|         |                                       |     |
|---------|---------------------------------------|-----|
| 13-1    | GENERAL .....                         | 110 |
| 13-2    | REMOVING EXISTING FACILITIES.....     | 110 |
| 13-2.01 | MAILBOXES.....                        | 110 |
| 13-2.02 | SIGNS.....                            | 111 |
| 13-2.03 | SURVEY MONUMENTS.....                 | 111 |
| 13-2.04 | LANDSCAPING IMPROVEMENTS.....         | 111 |
| 13-2.05 | ABANDONED UNDERGROUND FACILITIES..... | 111 |
| 13-2.06 | DRAINAGE FACILITIES .....             | 111 |
| 13-2.07 | FENCES .....                          | 112 |
| 13-2.08 | CONCRETE .....                        | 112 |
| 13-3    | MEASUREMENT AND PAYMENT .....         | 112 |

### **SECTION 14 – RESTORATION OF SURFACES**

|         |                               |     |
|---------|-------------------------------|-----|
| 14-1    | GENERAL .....                 | 114 |
| 14-2    | PRIVATE ROADS.....            | 114 |
| 14-3    | STREETS AND PARKING LOTS..... | 114 |
| 14-3.01 | AGGREGATE BASE.....           | 114 |
| 14-3.02 | ASPHALT CONCRETE.....         | 114 |
| 14-3.03 | SEAL COATS.....               | 115 |
| 14-3.04 | SHOULDERS.....                | 115 |
| 14-3.05 | CUTS IN NEW PAVEMENT.....     | 115 |
| 14-4    | CONCRETE .....                | 115 |
| 14-5    | PAVEMENT MARKINGS.....        | 116 |
| 14-6    | TEMPORARY PAVING .....        | 116 |
| 14-7    | MEASUREMENT AND PAYMENT ..... | 116 |

---

**SECTION 15 – CLEARING AND GRUBBING**

---

|         |   |     |
|---------|---|-----|
| 15-1    | GENERAL .....                                   | 118 |
| 15-1.01 | VEGETATION AND DEBRIS.....                      | 118 |
| 15-1.02 | TREES, SHRUBS, GROUND COVER, AND LAWNS .....    | 118 |
| 15-1.03 | DISPOSAL AND SALVAGE .....                      | 119 |
| 15-1.04 | ABANDONMENT OF CONDUITS AND<br>STRUCTURES ..... | 119 |
| 15-1.05 | SILT CONTROL.....                               | 120 |
| 15-1.06 | MISCELLANEOUS.....                              | 120 |
| 15-2    | PAYMENT .....                                   | 120 |

**SECTION 16 – WATER USED IN CONSTRUCTION**

---

|      |               |     |
|------|---------------|-----|
| 16-1 | GENERAL ..... | 121 |
| 16-2 | PAYMENT ..... | 121 |

**SECTION 17 – DUST CONTROL**

---

|      |                               |     |
|------|-------------------------------|-----|
| 17-1 | GENERAL .....                 | 122 |
| 17-2 | DUST PALLIATIVE.....          | 122 |
| 17-3 | MEASUREMENT AND PAYMENT ..... | 122 |

**SECTION 18 – EARTHWORK**

---

|          |  |     |
|----------|--|-----|
| 18-1     | GENERAL .....  | 123 |
| 18-2     | ROADWAY EXCAVATION.....  | 123 |
| 18-2.01  | GENERAL .....  | 123 |
| 18-2.02  | UNSUITABLE ROADWAY EXCAVATION AND<br>BACKFILL.....               | 123 |
| 18-2.03  | SURPLUS MATERIAL.....  | 123 |
| 18-2.04  | UNSUITABLE MATERIAL IN EMBANKMENTS.....                          | 123 |
| 18-2.05  | SUBGRADE PREPARATION`.....                                       | 124 |
| 18-2.05A | SUBGRADE SOILS – ROADWAY, CURB AND<br>GUTTER, AND SIDEWALKS..... | 125 |
| 18-2.06  | MEASUREMENT AND PAYMENT .....                                    | 126 |
| 18-3     | STRUCTURE EXCAVATION AND BACKFILL.....                           | 126 |
| 18-3.01  | GENERAL .....  | 126 |
| 18-3.02  | CONTROL DENSITY BACKFILL.....                                    | 127 |
| 18-3.03  | FINAL QUANTITY.....  | 127 |
| 18-3.04  | MEASUREMENT AND PAYMENT .....                                    | 127 |
| 18-4     | DITCH AND CHANNEL EXCAVATION.....                                | 127 |
| 18-4.01  | GENERAL .....  | 127 |
| 18-4.02  | GRADE CONTROL - LINED CHANNELS .....                             | 127 |
| 18-4.03  | UNSUITABLE DITCH AND CHANNEL EXCAVATION<br>AND BACKFILL.....     | 127 |
| 18-4.04  | UNSUITABLE OR SURPLUS MATERIAL DISPOSAL.....                     | 127 |
| 18-4.05  | CHANNEL BACKFILL.....  | 128 |
| 18-4.06  | CHANNEL EMBANKMENTS .....  | 128 |
| 18-4.07  | PIPE ADJUSTMENTS.....  | 128 |
| 18-5     | UNSUITABLE MATERIAL EXCAVATION.....                              | 128 |
| 18-5.01  | GENERAL .....  | 128 |
| 18-5.02  | BACKFILL.....  | 129 |

---

|      |         |                                |     |
|------|---------|--------------------------------|-----|
|      | 18-5.03 | GEOTEXTILE MATERIAL.....       | 129 |
|      | 18-5.04 | APPROXIMATE QUANTITY .....     | 129 |
|      | 18-5.05 | PAYMENT .....                  | 130 |
| 18-6 |         | IMPORTED BORROW .....          | 130 |
|      | 18-6.01 | GENERAL .....                  | 130 |
|      | 18-6.02 | AGREEMENTS.....                | 131 |
|      | 18-6.03 | PLACEMENT.....                 | 131 |
| 18-7 |         | SURPLUS MATERIAL DISPOSAL..... | 131 |
|      | 18-7.01 | GENERAL .....                  | 131 |
|      | 18-7.02 | AGREEMENT .....                | 131 |
|      | 18-7.03 | PERMITS.....                   | 131 |
|      | 18-7.04 | PAYMENT .....                  | 132 |
| 18-8 |         | CLASS "C" SUBGRADE.....        | 132 |
|      | 18-8.01 | GENERAL .....                  | 132 |
|      | 18-8.02 | PREPARATION .....              | 132 |
|      | 18-8.03 | PAYMENT .....                  | 133 |

## **SECTION 19 – TRENCH EXCAVATION, BEDDING AND BACKFILL**

|      |          |   |     |
|------|----------|---|-----|
| 19-1 |          | TRENCH EXCAVATION.....                        | 134 |
|      | 19-1.01  | EXPLORATORY EXCAVATION .....                  | 134 |
|      | 19-1.02  | TRENCH WIDTH.....                             | 134 |
|      | 19-1.02A | STORM DRAIN PIPE.....                         | 134 |
|      | 19-1.02B | SEWER PIPE .....                              | 134 |
|      | 19-1.02C | WATER PIPE.....                               | 134 |
|      | 19-1.03  | PAVEMENT CUTTING .....                        | 135 |
|      | 19-1.04  | MAXIMUM LENGTH OF OPEN TRENCH.....            | 135 |
|      | 19-1.05  | CONTROL OF GROUNDWATER.....                   | 135 |
|      | 19-1.06  | SHORING AND BRACING.....                      | 135 |
|      | 19-1.07  | SPECIAL FOUNDATION TREATMENT .....            | 136 |
|      | 19-1.08  | EXCAVATION METHOD .....                       | 137 |
|      | 19-1.09  | PAYMENT .....                                 | 137 |
| 19-2 |          | PIPE BEDDING AND BACKFILLING OF TRENCHES..... | 137 |
|      | 19-2.01  | PIPE BEDDING.....                             | 137 |
|      | 19-2.01A | SEWER.....                                    | 137 |
|      | 19-2.01B | STORM DRAIN.....                              | 138 |
|      | 19-2.01C | WATER DISTRIBUTION SYSTEMS.....               | 139 |
|      | 19-2.02  | INITIAL BACKFILL.....                         | 139 |
|      | 19-2.02A | STORM DRAIN.....                              | 139 |
|      | 19-2.02C | WATER DISTRIBUTION SYSTEMS.....               | 139 |
|      | 19-2.03  | TRENCH BACKFILL.....                          | 140 |
|      | 19-2.03A | CUT OFF COLLARS.....                          | 141 |
|      | 19-2.03B | BACKFILL WITHIN EXISTING STREETS .....        | 142 |
|      | 19-2.04  | PAYMENT .....                                 | 142 |

## **SECTION 20 – LANDSCAPING**

|      |         |                           |     |
|------|---------|---------------------------|-----|
| 20-1 |         | GENERAL .....             | 143 |
| 20-2 |         | MATERIALS.....            | 143 |
|      | 20-2.01 | ROOT CONTROL BARRIER..... | 143 |
|      | 20-2.02 | TOPSOIL .....             | 143 |
|      | 20-2.03 | SOIL AMENDMENT .....      | 143 |
|      | 20-2.04 | LIQUID GREEN DYE .....    | 143 |

|      |           |  |     |
|------|-----------|--|-----|
|      | 20-2.05   | MULCH .....  | 144 |
| 20-3 |           | EROSION CONTROL.....   | 144 |
|      | 20-3.01   | SEEDING AND FERTILIZING.....   | 144 |
|      | 20-3.02   | MEASUREMENT AND PAYMENT .....  | 145 |
| 20-4 |           | PLANTING .....   | 145 |
|      | 20-4.01   | PESTICIDES.....  | 145 |
|      | 20-4.02   | PREPARING PLANTING AREAS.....  | 145 |
|      | 20-4.03   | HEADER BOARDS .....  | 146 |
|      | 20-4.04   | PLANTING .....   | 146 |
|      | 20-4.04.A | PREPARATION FOR GROUND COVERS.....                                   | 148 |
|      | 20-4.04.B | PREPARATION FOR TREES AND SHRUBS.....                                | 148 |
|      | 20-4.04.C | PREPARATION FOR TURF .....   | 149 |
|      | 20-4.05   | WATERING.....  | 150 |
|      | 20-4.06   | PLANT REPLACEMENT.....   | 150 |
|      | 20-4.07   | PLANT ESTABLISHMENT WORK .....                                       | 150 |
|      | 20-4.08   | INSPECTION FOR PLANT ESTABLISHMENT WORK.....                         | 152 |
|      | 20-4.09   | MEASUREMENT AND PAYMENT .....  | 152 |
| 20-5 |           | IRRIGATION SYSTEMS .....   | 152 |
|      | 20-5.01   | MAINTAIN EXISTING WATER SUPPLY .....                                 | 152 |
|      | 20-5.02   | REMOVE EXISTING PLANTS FOR TRENCHING.....                            | 153 |
|      | 20-5.03   | ELECTRICAL SERVICE FOR ELECTRIC<br>AUTOMATIC IRRIGATION SYSTEMS..... | 153 |
|      | 20-5.03.A | COMPONENTS.....  | 153 |
|      | 20-5.03.B | CONTROLLERS.....   | 153 |
|      | 20-5.03.C | CONTROL WIRE, ELECTRICAL CONDUIT AND<br>PULL BOXES .....             | 154 |
|      | 20-5.03.D | TESTING.....   | 154 |
|      | 20-5.04   | INSTALLATION .....   | 155 |
|      | 20-5.04.A | GENERAL .....  | 155 |
|      | 20-5.04.B | IRRIGATION SLEEVING.....   | 155 |
|      | 20-5.04.C | WATER LINE CROSSOVERS.....   | 156 |
|      | 20-5.04.D | TRENCHING AND BACKFILLING.....                                       | 156 |
|      | 20-5.05   | PIPE .....   | 157 |
|      | 20-5.05.A | SUBSURFACE DRIPPERLINE .....   | 158 |
|      | 20-5.05.B | VALVES AND VALVE BOXES.....  | 159 |
|      | 20-5.05.C | QUICK COUPLING VALVE.....  | 159 |
|      | 20-5.05.D | BACKFLOW PREVENTERS.....   | 159 |
|      | 20-5.05.E | MASTER VALVE/FLOW METER ASSEMBLY.....                                | 160 |
|      | 20-5.05.F | AIR VACUUM RELIEF VALVE .....  | 160 |
|      | 20-5.05.G | FLUSH VALVE .....  | 160 |
|      | 20-5.05.H | SPRINKLERS AND EMITTERS.....   | 161 |
|      | 20-5.05.I | PRESSURE TESTING.....  | 161 |
|      | 20-5.05.J | REPAIRS AND COVERAGE .....   | 162 |
|      | 20-5.06   | MEASUREMENT AND PAYMENT .....  | 162 |
| 20-6 |           | AS BUILT DRAWINGS AND CONTROLLER CHARTS .....                        | 162 |

**SECTION 21 – FINISHING ROADWAY**

|      |               |     |
|------|---------------|-----|
| 21-1 | GENERAL ..... | 164 |
| 21-2 | PAYMENT ..... | 164 |

---

**SECTION 22 – BASE MATERIAL**

---

|      |               |     |
|------|---------------|-----|
| 22-1 | GENERAL ..... | 165 |
|------|---------------|-----|

**SECTION 23 – ASPHALT CONCRETE**

---

|           |   |     |
|-----------|---|-----|
| 23-1      | GENERAL .....                                       | 166 |
| 23-2      | MIX FORMULA AND DESIGN .....                        | 166 |
| 23-3      | AGGREGATE .....                                     | 166 |
| 23-4      | RECYCLED ASPHALT PAVEMENT .....                     | 166 |
| 23-5      | HAULING EQUIPMENT .....                             | 168 |
| 23-6      | CONSTRUCTION PLAN .....                             | 169 |
| 23-7      | ASPHALT CONCRETE PLACEMENT METHOD .....             | 169 |
| 23-7.01   | GENERAL .....                                       | 169 |
| 23-7.02   | PRE-OVERLAY PREPARATION .....                       | 170 |
| 23-7.03   | SPREADING .....                                     | 171 |
| 23-7.03.A | HAND SPREADING .....                                | 172 |
| 23-7.03.B | MECHANICAL SPREADING EQUIPMENT .....                | 172 |
| 23-7.04   | JOINTS .....  | 173 |
| 23-7.05   | COMPACTING .....                                    | 173 |
| 23-8      | ASPHALT CONCRETE PLACEMENT ACCEPTANCE TESTING ..... | 174 |
| 23-8.01   | PAVEMENT DENSITY TESTING .....                      | 174 |
| 23-8.01.A | LOT SIZES .....                                     | 174 |
| 23-8.01.B | LABORATORY DENSITY .....                            | 174 |
| 23-8.01.C | CORE DENSITY .....                                  | 174 |
| 23-8.02   | PAY FACTORS .....                                   | 175 |
| 23-9      | ASPHALT RUBBER HOT MIX-GAP GRADED (ARHM-GG) .....   | 175 |
| 23-9.01   | TYPE 1 ASPHALT-RUBBER BINDER (PG 64-16) .....       | 177 |
| 23-9.02   | TYPE 2 ASPHALT-RUBBER BINDER .....                  | 177 |
| 23-9.03   | AGGREGATE .....                                     | 179 |
| 23-9.04   | EQUIPMENT .....                                     | 179 |
| 23-9.04.A | HAULERS .....                                       | 179 |
| 23-9.04.B | ASPHALT HEATING TANK .....                          | 179 |
| 23-9.04.C | MECHANICAL BLENDER .....                            | 179 |
| 23-9.04.D | STORAGE/REACTION TANK .....                         | 180 |
| 23-9.04.E | SUPPLY SYSTEM .....                                 | 180 |
| 23-9.04.F | TEMPERATURE GAGE .....                              | 180 |
| 23-9.05   | PLACEMENT .....                                     | 180 |
| 23-10     | MEASUREMENT AND PAYMENT .....                       | 180 |

**SECTION 24 – SIDE FORMS AND HEADERS**

---

|      |                         |     |
|------|-------------------------|-----|
| 24-1 | GENERAL .....           | 182 |
| 24-2 | FORM JOINTS .....       | 182 |
| 24-3 | TIMBER SIDE FORMS ..... | 182 |
| 24-4 | METAL SIDE FORMS .....  | 182 |
| 24-5 | FORM MAINTENANCE .....  | 183 |
| 24-6 | PAYMENT .....           | 183 |

**SECTION 25 – PORTLAND CEMENT CONCRETE PAVEMENT**

---

|      |                  |     |
|------|------------------|-----|
| 25-1 | GENERAL .....    | 184 |
| 25-2 | SUBGRADE .....   | 184 |
| 25-3 | SIDE FORMS ..... | 184 |

|       |  |     |
|-------|--|-----|
| 25-4  | CONCRETE CUTTING .....                         | 184 |
| 25-5  | EXPANSION JOINTS IN ALLEY PAVEMENT.....        | 184 |
| 25-6  | PLACING CONCRETE PAVEMENT.....                 | 184 |
| 25-7  | FINISHING CONCRETE PAVEMENT.....               | 185 |
| 25-8  | CURING PORTLAND CEMENT CONCRETE PAVEMENT ..... | 185 |
| 25-9  | PROTECTION OF PAVEMENT .....                   | 185 |
| 25-10 | PAVEMENT DAMAGE AND REPAIR.....                | 185 |
| 25-11 | MEASUREMENT .....                              | 186 |
| 25-12 | PAYMENT .....                                  | 186 |

## **SECTION 26 – COLD PLANE ASPHALT CONCRETE PAVEMENT**

|      |                                  |     |
|------|----------------------------------|-----|
| 26-1 | GENERAL .....                    | 187 |
| 26-2 | PAVEMENT KEY CUTTING .....       | 187 |
| 26-3 | PAVEMENT PLANING .....           | 188 |
| 26-4 | PLANED PAVEMENT CONFORMS.....    | 188 |
| 26-5 | PAVEMENT REINFORCING FABRIC..... | 189 |
| 26-6 | MEASUREMENT .....                | 189 |
| 26-7 | PAYMENT .....                    | 190 |

## **SECTION 27 – CURBS, GUTTERS, SIDEWALKS, AND DRAINAGE STRUCTURES**

|         |  |     |
|---------|--|-----|
| 27-1    | GENERAL .....  | 191 |
| 27-2    | FORMS.....   | 191 |
| 27-3    | CONCRETE IN CURBS, GUTTERS, AND SIDEWALKS .....  | 191 |
| 27-3.01 | EXPANSION JOINTS, WEAKENED PLANE JOINTS,<br>AND SCORE MARKS.....   | 192 |
| 27-3.02 | FINISHING CONCRETE SURFACES .....  | 192 |
| 27-3.03 | CURING OF CONCRETE.....  | 192 |
| 27-3.04 | ALLOWANCE FOR SIGNS IN MEDIAN AND<br>TRAFFIC ISLANDS .....   | 193 |
| 27-3.05 | MINOR CURB AND GUTTER AND SIDEWALK<br>REPLACEMENT.....   | 193 |
| 27-3.06 | CONCRETE TESTING.....  | 193 |
| 27-4    | DAMAGE REPAIRS.....  | 193 |
| 27-5    | SLOPE OF SIDEWALKS.....  | 194 |
| 27-6    | CURB DOWELS AND REINFORCEMENT .....  | 194 |
| 27-7    | EXTRUDED CONSTRUCTION.....   | 194 |
| 27-8    | CURB RAMPS AND DRIVEWAYS.....  | 195 |
| 27-9    | RECONSTRUCTION OF CURBS, GUTTER, AND SIDEWALK.....   | 195 |
| 27-10   | RECONSTRUCTION OF CURBS, GUTTER, AND CURB AND<br>GUTTER TO ACCOMMODATE SEWER AND STORM DRAIN<br>SERVICE INSTALLATION AND DRIVEWAYS ..... | 195 |
| 27-11   | CURB AND GUTTER TESTING AND TOLERANCE.....   | 195 |
| 27-12   | RESERVED.....  | 196 |
| 27-13   | DROP INLETS AND CATCH BASINS .....   | 196 |
| 27-14   | MEASUREMENT .....  | 196 |
| 27-15   | PAYMENT .....  | 197 |

## **SECTION 28 – PILING**

|      |               |     |
|------|---------------|-----|
| 28-1 | GENERAL ..... | 199 |
|------|---------------|-----|

---

**SECTION 28 – PRESTRESS CONCRETE**

---

|      |               |     |
|------|---------------|-----|
| 29-1 | GENERAL ..... | 200 |
|------|---------------|-----|

**SECTION 30 – CONCRETE STRUCTURES**

---

|       |  |     |
|-------|--|-----|
| 30-1  | GENERAL .....                                  | 201 |
| 30-2  | FOOTINGS.....                                  | 201 |
| 30-3  | FORMS.....                                     | 201 |
| 30-4  | REMOVAL OF FORMS.....                          | 202 |
| 30-5  | REINFORCEMENT .....                            | 202 |
| 30-6  | MIXING AND TRANSPORTING.....                   | 202 |
| 30-7  | PLACING CONCRETE.....                          | 202 |
|       | 30-7.01    GENERAL .....                       | 202 |
|       | 30-7.02    PLACEMENT.....                      | 203 |
|       | 30-7.03    VIBRATING.....                      | 203 |
|       | 30-7.04    CONCRETE TESTING.....               | 203 |
| 30-8  | BONDING .....                                  | 204 |
| 30-9  | CONCRETE PLACED UNDER WATER.....               | 204 |
| 30-10 | EXPANSION JOINTS .....                         | 204 |
| 30-11 | CONSTRUCTION JOINTS.....                       | 204 |
| 30-12 | WATERSTOPS.....                                | 205 |
| 30-13 | CURING .....                                   | 205 |
| 30-14 | PROTECTING CONCRETE .....                      | 205 |
| 30-15 | SURFACE FINISH.....                            | 205 |
|       | 30-15.01    GENERAL .....                      | 205 |
|       | 30-15.02    SMOOTH FORM FINISH (SACKING).....  | 206 |
|       | 30-15.03    ORDINARY SURFACE FINISH.....       | 206 |
|       | 30-15.04    TOLERANCE ON CONCRETE PAVING ..... | 206 |
| 30-16 | CONCRETE REPAIR.....                           | 207 |
|       | 30-16.01    GENERAL .....                      | 207 |
|       | 30-16.02    REPLACEMENT WITH CONCRETE.....     | 207 |
|       | 30-16.03    MORTAR (DRY PACK).....             | 207 |
|       | 30-16.04    SHOTCRETE.....                     | 207 |
|       | 30-16.05    TOPPING.....                       | 207 |
| 30-17 | MEASUREMENT AND PAYMENT .....                  | 207 |

**SECTION 31 – REINFORCEMENT**

---

|      |                               |     |
|------|-------------------------------|-----|
| 31-1 | GENERAL .....                 | 209 |
| 31-2 | MEASUREMENT AND PAYMENT ..... | 209 |

**SECTION 32 – WATERPROOFING**

---

|      |               |     |
|------|---------------|-----|
| 32-1 | GENERAL ..... | 210 |
|------|---------------|-----|

**SECTION 33 – STEEL STRUCTURES**

---

|      |               |     |
|------|---------------|-----|
| 33-1 | GENERAL ..... | 211 |
| 33-2 | PAYMENT ..... | 211 |

**SECTION 34 – SIGNS**

---

|      |                               |     |
|------|-------------------------------|-----|
| 34-1 | OVERHEAD SIGN STRUCTURES..... | 212 |
| 34-2 | ROADSIDE SIGNS .....          | 212 |

|         |                                    |     |
|---------|------------------------------------|-----|
| 34-2.01 | SIGN PANEL FASTENING HARDWARE..... | 212 |
| 34-2.02 | PARK SIGNS.....                    | 212 |
| 34-2.03 | SIGN PANEL INSTALLATION.....       | 212 |
| 34-3    | MEASUREMENT AND PAYMENT.....       | 212 |

### **SECTION 35 – TIMBER STRUCTURES**

|      |              |     |
|------|--------------|-----|
| 35-1 | GENERAL..... | 214 |
|------|--------------|-----|

### **SECTION 36 – CAST IN-PLACE CONCRETE PIPE (CIPCP)**

|           |  |     |
|-----------|--|-----|
| 36-1      | GENERAL.....                                 | 215 |
| 36-2      | PIPEMAKING EQUIPMENT.....                    | 215 |
| 36-3      | TRENCH EXCAVATION.....                       | 215 |
| 36-4      | SPECIAL FOUNDATION TREATMENT.....            | 215 |
| 36-5      | CONCRETE.....                                | 216 |
| 36-6      | PLACING CONCRETE.....                        | 216 |
| 36-7      | START AND CLOSE SECTIONS.....                | 217 |
| 36-8      | CONSTRUCTION JOINTS.....                     | 217 |
| 36-9      | FINISH.....                                  | 217 |
| 36-10     | FORMS.....                                   | 218 |
| 36-11     | CURING.....                                  | 218 |
| 36-12     | FIELD QUALITY CONTROL.....                   | 219 |
| 36-12.01  | PLACEMENT TESTS.....                         | 219 |
| 36-12.01A | REJECTION.....                               | 219 |
| 36-12.02  | CRACK REPAIR.....                            | 220 |
| 36-13     | REIMBURSEMENT FOR FIELD QUALITY CONTROL..... | 221 |
| 36-14     | BACKFILL.....                                | 221 |
| 36-15     | LOADING DURING CURING.....                   | 221 |
| 36-16     | MEASUREMENT AND PAYMENT.....                 | 221 |

### **SECTION 37 – BORING AND JACKING**

|      |  |     |
|------|--|-----|
| 37-1 | GENERAL.....                                       | 223 |
| 37-2 | DIRECT JACKING REINFORCED CONCRETE PIPE.....       | 223 |
| 37-3 | INSTALLATION OF CONDUCTOR PIPE.....                | 223 |
| 37-4 | INSTALLING CARRIER PIPE INSIDE CONDUCTOR PIPE..... | 223 |
| 37-5 | VOIDS.....   | 224 |
| 37-6 | TOLERANCES.....                                    | 224 |
| 37-7 | DRY BORING UNDER CURB, GUTTER AND SIDEWALK.....    | 224 |
| 37-8 | WET BORING OF SMALL DIAMETER PIPELINES.....        | 225 |
| 37-9 | MEASUREMENT AND PAYMENT.....                       | 225 |

### **SECTION 38 – STORM DRAIN CONSTRUCTION**

|         |                                 |     |
|---------|---------------------------------|-----|
| 38-1    | GENERAL.....                    | 226 |
| 38-2    | MATERIALS.....                  | 226 |
| 38-2A   | CAUSES FOR REJECTION.....       | 226 |
| 38-3    | EXCAVATION AND BEDDING.....     | 227 |
| 38-4    | LAYING PIPE.....                | 227 |
| 38-5    | STORM DRAIN INLET LATERALS..... | 228 |
| 38-6    | PIPE JOINTS.....                | 229 |
| 38-7    | PROTECTIVE COVERING.....        | 229 |
| 38-7.01 | STORM DRAIN PIPE.....           | 229 |



|                  |  |                                     |
|------------------|--|-------------------------------------|
| 38-8             | BACKFILLING PIPE TRENCHES .....  | 229                                 |
| 38-9             | TESTING OF PIPE.....   | 229                                 |
| 38-9.01          | TESTS FOR OBSTRUCTIONS.....  | 229                                 |
| 38-9.02          | TESTS FOR LEAKAGE.....   | 229                                 |
| 38-9.02.A        | AIR TEST FOR LEAKAGE - STORM DRAIN.....                                    | 229                                 |
| 38-9.02.A.(1)    | PLUG RESTRAINT.....  | 230                                 |
| 38-9.02.A.(2)    | RELIEF VALVE.....  | 230                                 |
| 38-9.02.A.(3)    | EQUIPMENT .....  | 230                                 |
| 38-9.02.A.(3)(A) | PLUG DESIGN.....   | 230                                 |
| 38-9.02.A.(3)(B) | SINGULAR CONTROL PANEL.....  | 230                                 |
| 38-9.02.A.(3)(C) | EQUIPMENT CONTROLS .....   | 231                                 |
| 38-9.02.A.(3)(D) | SEPARATE HOSES.....  | 231                                 |
| 38-9.02.A.(3)(E) | PNEUMATIC PLUGS .....  | 231                                 |
| 38-9.02.A.(4)    | LINE PREPARATION.....  | 231                                 |
| 38-9.02.A.(4)(A) | LATERALS, STUBS AND FITTINGS .....   | 231                                 |
| 38-9.02.A.(4)(B) | PIPE WETTING.....  | 231                                 |
| 38-9.02.A.(5)    | TEST PROCEDURE.....  | 231                                 |
| 38-9.02.A.(5)(A) | PLUG INSTALLATION AND TESTING.....   | 231                                 |
| 38-9.02.A.(5)(B) | LINE PRESSURIZATION .....  | 232                                 |
| 38-9.02.A.(5)(C) | PRESSURE STABILIZATION.....  | 232                                 |
| 38-9.02.A.(5)(D) | TIMING PRESSURE LOSS.....  | 232                                 |
| 38-9.02.A.(5)(E) | DETERMINATION OF LINE ACCEPTANCE .....                                     | 232                                 |
| 38-9.02.A.(5)(F) | DETERMINATION OF LINE FAILURE.....   | 232                                 |
| 38-9.02.A.(5)(G) | LINE REPAIR OR REPLACEMENT .....   | 233                                 |
| 38-9.02.A.(6)    | DETERMINATION OF GROUNDWATER<br>ELEVATION AND AIR PRESSURE ADJUSTMENT..... | 233                                 |
| 38-9.02.A.(6)(A) | APPLICABILITY.....   | 233                                 |
| 38-9.02.A.(6)(B) | PIPE NIPPLE INSTALLATION.....  | 233                                 |
| 38-9.02.A.(6)(C) | GROUNDWATER ELEVATION.....   | 233                                 |
| 38-9.02.A.(6)(D) | AIR PRESSURE ADJUSTMENT.....   | 234                                 |
| 38-9.02.A.(6)(E) | MAXIMUM TEST PRESSURE.....   | 235                                 |
| 38-9.02.A.(6)(F) | RE-SEALING OF PIPE NIPPLES.....  | 235                                 |
| 38-9.02.A.(7)    | TEST TIMES .....   | 235                                 |
| 38-9.02.A.(7)(A) | TEST TIME CRITERIA .....   | 235                                 |
| 38-9.02.A.(7)(B) | TEST TIME CALCULATION.....   | 235                                 |
| 38-9.02.A.(7)(C) | TESTING MAIN STORM DRAINS WITH LATERAL<br>CONNECTORS .....                 | 236                                 |
| 38-9.02.A.(7)(D) | SPECIFIED TIME TABLE.....  | 236                                 |
| 38-9.02.B        | HYDROSTATIC TEST FOR LEAKAGE – STORM<br>DRAIN .....                        | 237                                 |
| 38-9.02.B.(1)    | WATER EXFILTRATION TEST .....  | 237                                 |
| 38-9.03          | TESTS FOR DEFLECTION.....  | 237                                 |
| 38-9.03.A        | SEWER.....   | <b>ERROR! BOOKMARK NOT DEFINED.</b> |
| 38-9.04          | TELEVISION INSPECTION – STORM DRAINS.....                                  | 237                                 |
| 38-9.04.A        | SAFETY.....  | 238                                 |
| 38-9.04.B        | EQUIPMENT .....  | 238                                 |
| 38-9.04.B.(1)    | CAMERA .....   | 238                                 |
| 38-9.04.B.(2)    | COMPUTER SYSTEM.....   | <b>ERROR! BOOKMARK NOT DEFINED.</b> |
| 38-9.04.B.(3)    | LIGHTING.....  | 239                                 |
| 38-9.04.C        | PRE-REHABILITATION TVI INSPECTION.....                                     | 239                                 |
| 38-9.04.C.(1)    | PRE-LINING VIDEO .....   | <b>ERROR! BOOKMARK NOT DEFINED.</b> |
| 38-9.04.D        | POST REHABILITATION AND NEWLY<br>CONSTRUCTED DRAIN PIPELINES .....         | 239                                 |

|                  |  |     |
|------------------|--|-----|
| 38-9.04.E        | TVI INSPECTION REPORT AND VIDEO .....              | 239 |
| 38-9.04.F.(1)    | PROCEDURE .....                                    | 240 |
| 38-9.04.F.(2)    | TIMING.....  | 240 |
| 38-9.04.F.(3)    | RESERVED.....                                      | 241 |
| 38-9.04.F.(4)    | INITIAL SCREEN TEXT AND AUDIO<br>INFORMATION.....  | 241 |
| 38-9.04.F.(4)(A) | VIDEO INFORMATION.....                             | 241 |
| 38-9.04.F.(4)(B) | AUDIO INFORMATION .....                            | 241 |
| 38-9.04.F.(5)    | RUNNING SCREEN TEXT AND ENDING SCREEN<br>TEXT..... | 241 |
| 38-9.04.F.(6)    | TVI RECORDING LABELS .....                         | 242 |
| 38-9.04.G        | NON-CONFORMING TVI INSPECTION.....                 | 242 |
| 38-9.05          | LAMPING OF STORM DRAIN INLET LATERALS .....        | 242 |
| 38-9.06          | PIPELINE ACCEPTANCE CRITERIA.....                  | 243 |
| 38-10            | RESTORATION OF SURFACES .....                      | 244 |
| 38-11            | MEASUREMENT AND PAYMENT .....                      | 244 |

### **SECTION 39 – MANHOLES**

|         |   |     |
|---------|---|-----|
| 39-1    | GENERAL .....                               | 245 |
| 39-2    | PRECAST CONCRETE MANHOLES.....              | 245 |
| 39-2.01 | PRECAST CONCRETE STORM DRAIN MANHOLES ..... | 245 |
| 39-3    | SADDLE MANHOLES .....                       | 247 |
| 39-3.01 | SADDLE STORM DRAIN MANHOLES.....            | 247 |
| 39-4    | MANHOLE TESTING .....                       | 247 |
| 39-4.01 | STORM DRAIN MANHOLES.....                   | 247 |
| 39-4.02 | MANHOLE PIPE ZONE BACKFILL.....             | 248 |
| 39-5    | ADJUST STORM DRAIN MANHOLES TO GRADE.....   | 248 |
| 39-6    | RECONSTRUCT STORM DRAIN MANHOLES .....      | 249 |
| 39-7    | ABANDON STORM DRAIN MANHOLES.....           | 249 |
| 39-8    | MEASUREMENT AND PAYMENT .....               | 249 |

### **SECTION 40 – MISCELLANEOUS FACILITIES**

|      |               |     |
|------|---------------|-----|
| 40-1 | RESERVED..... | 251 |
|------|---------------|-----|

### **SECTION 41 – WATER DISTRIBUTION SYSTEMS**

|      |               |     |
|------|---------------|-----|
| 41-1 | GENERAL ..... | 252 |
| 41-2 | PAYMENT ..... | 252 |

### **SECTION 42 – RELOCATION AND MAINTENANCE OF UTILITY FACILITIES**

|      |                                       |     |
|------|---------------------------------------|-----|
| 42-1 | RELOCATION OF UTILITY FACILITIES..... | 253 |
| 42-2 | MEASUREMENT AND PAYMENT .....         | 253 |

### **SECTION 43 – CLEANING PIPELINES**

|      |                               |     |
|------|-------------------------------|-----|
| 43-1 | GENERAL .....                 | 254 |
| 43-2 | MEASUREMENT AND PAYMENT ..... | 254 |

### **SECTION 44 – SHOTCRETE, CAST CONCRETE CHANNEL LINING, AND GROUTED COBBLE**

|      |                |     |
|------|----------------|-----|
| 44-1 | SHOTCRETE..... | 255 |
|------|----------------|-----|

|         |                                    |     |
|---------|------------------------------------|-----|
| 44-1.01 | DESCRIPTION .....                  | 255 |
| 44-1.02 | MATERIALS.....                     | 255 |
| 44-1.03 | PROPORTIONS .....                  | 255 |
| 44-1.04 | MIXING.....                        | 255 |
| 44-1.05 | SURFACE PREPARATION.....           | 255 |
| 44-1.06 | PLACING.....                       | 256 |
| 44-1.07 | CURING AND PROTECTION .....        | 256 |
| 44-1.08 | REINFORCEMENT .....                | 256 |
| 44-1.09 | EXPANSION JOINTS .....             | 256 |
| 44-1.10 | MEASUREMENT AND PAYMENT .....      | 256 |
| 44-2    | CAST CONCRETE CHANNEL LINING ..... | 257 |
| 44-2.01 | DESCRIPTION .....                  | 257 |
| 44-2.02 | MATERIALS.....                     | 257 |
| 44-2.03 | PLACEMENT AND THICKNESS.....       | 257 |
| 44-2.04 | REINFORCEMENT .....                | 257 |
| 44-2.05 | JOINTS .....                       | 258 |
| 44-2.06 | WEEP HOLES.....                    | 258 |
| 44-2.07 | CUTOFF WALLS .....                 | 258 |
| 44-2.08 | FINISHING .....                    | 259 |
| 44-2.09 | CURING AND PROTECTION .....        | 259 |
| 44-2.10 | MEASUREMENT AND PAYMENT .....      | 259 |
| 44-3    | GROUTED COBBLES .....              | 259 |
| 44-3.01 | DESCRIPTION .....                  | 259 |
| 44-3.02 | MATERIALS AND PLACEMENT.....       | 259 |
| 44-3.03 | MEASUREMENT AND PAYMENT .....      | 260 |

#### **SECTION 45 – CHAIN LINK FENCE**

|      |                               |     |
|------|-------------------------------|-----|
| 45-1 | GENERAL .....                 | 261 |
| 45-2 | MATERIALS.....                | 261 |
| 45-3 | CONSTRUCTION .....            | 261 |
| 45-4 | MEASUREMENT AND PAYMENT ..... | 261 |

#### **SECTION 46 – SURVEY MONUMENTS**

|      |                               |     |
|------|-------------------------------|-----|
| 46-1 | GENERAL .....                 | 262 |
| 46-2 | MATERIALS.....                | 262 |
| 46-3 | CONSTRUCTION .....            | 262 |
| 46-4 | MEASUREMENT AND PAYMENT ..... | 263 |

#### **SECTION 47 – RAILINGS AND BARRIERS**

|      |               |     |
|------|---------------|-----|
| 47-1 | GENERAL ..... | 264 |
|------|---------------|-----|

#### **SECTION 48 – TRAFFIC STRIPES AND PAVEMENT MARKINGS**

|      |   |     |
|------|---|-----|
| 48-1 | GENERAL .....   | 265 |
| 48-2 | THERMOPLASTIC TRAFFIC STRIPES AND PAVEMENT<br>MARKINGS..... | 265 |
| 48-3 | PLACEMENT .....   | 265 |
| 48-4 | MEASUREMENT AND PAYMENT .....                               | 265 |

**SECTION 49 – SIGNALS, LIGHTING AND ELECTRICAL SYSTEMS**

|           |   |     |
|-----------|---|-----|
| 49-1      | GENERAL .....   | 267 |
| 49-1.01   | DEFINITIONS .....   | 267 |
| 49-1.02   | ABBREVIATIONS.....  | 267 |
| 49-1.04   | EQUIPMENT LIST AND DRAWINGS.....  | 267 |
| 49-1.05   | ORDERING OF SIGNAL AND LIGHTING<br>EQUIPMENT .....  | 268 |
| 49-1.06   | MAINTAINING EXISTING AND TEMPORARY<br>ELECTRICAL SYSTEMS.....                                       | 268 |
| 49-1.07   | SCHEDULING OF WORK .....  | 269 |
| 49-1.08   | SAFETY PRECAUTIONS.....   | 269 |
| 49-1.09   | INSPECTION .....  | 269 |
| 49-2      | MATERIALS AND INSTALLATION.....   | 269 |
| 49-2.01   | TRENCH EXCAVATION AND BACKFILL.....   | 269 |
| 49-2.02   | REMOVING AND REPLACING IMPROVEMENTS.....  | 270 |
| 49-2.03   | FOUNDATIONS.....  | 270 |
| 49-2.04   | STANDARDS, STEEL PEDESTALS AND POSTS .....  | 270 |
| 49-2.04.A | ALUMINUM AND CONCRETE STREET LIGHT<br>STANDARDS .....   | 271 |
| 49-2.04.B | PLACEMENT OF STANDARDS, ENCLOSURES,<br>POSTS AND ASSOCIATED DEVICES .....                           | 272 |
| 49-2.04.C | FINAL LOCATION OF TRAFFIC SIGNAL POLES.....   | 272 |
| 49-2.05   | CONDUIT .....   | 272 |
| 49-2.06   | PULL BOXES .....  | 275 |
| 49-2.07   | CONDUCTORS AND CABLES.....  | 276 |
| 49-2.07.A | SIGNAL INTERCONNECT CABLE.....  | 277 |
| 49-2.07.B | INTERCONNECT CABLE TESTING AFTER<br>INSTALLATION .....  | 277 |
| 49-2.08   | SPLICES.....  | 278 |
| 49-2.09   | BONDING AND GROUNDING.....  | 278 |
| 49-2.10   | SERVICE.....  | 278 |
| 49-2.10.A | METERED SERVICE (120/208 VOLT, 120/240<br>VOLT).....  | 279 |
| 49-2.10.B | METERED SERVICE WITH ENCAPSULATED STEP-<br>DOWN TRANSFORMER (277/480 VOLT TO 120-<br>240 VOLT)..... | 280 |
| 49-2.10.C | UNMETERED SERVICE (120/208 VOLT, 120/240<br>VOLT).....  | 282 |
| 49-2.10.D | UNMETERED SERVICE (277/480 VOLT).....   | 282 |
| 49-2.10.E | UNMETERED SERVICE WITH ENCAPSULATED<br>STEP-DOWN TRANSFORMER (277/480 VOLT TO<br>120/240 VOLT)..... | 283 |
| 49-2.11   | TESTING.....  | 284 |
| 49-3      | CONTROLLER ASSEMBLIES.....  | 285 |
| 49-4      | TRAFFIC SIGNAL FACES AND FITTINGS .....   | 285 |
| 49-4.01   | VEHICLE SIGNAL FACES AND SIGNAL HEADS .....   | 285 |
| 49-4.02   | DIRECTIONAL LOUVERS.....  | 285 |
| 49-4.03   | BACKPLATES .....  | 285 |
| 49-4.04   | ACCESSIBLE PEDESTRIAN SIGNALS .....   | 286 |
| 49-5      | DETECTORS.....  | 286 |
| 49-5.01   | VEHICLE DETECTORS .....   | 286 |
| 49-5.01.A | CONSTRUCTION MATERIALS.....   | 286 |
| 49-5.01.B | INSTALLATION DETAILS.....   | 287 |

|           |  |     |
|-----------|--|-----|
| 49-5.02   | OPTICOM CABLE AND DETECTORS .....                | 289 |
| 49-6      | LIGHTING.....                                    | 290 |
| 49-6.01   | LED LUMINAIRES .....                             | 290 |
| 49-6.02   | RESERVED.....                                    | 296 |
| 49-6.03   | INTERNALLY ILLUMINATED STREET NAME<br>SIGNS..... | 296 |
| 49-6.04   | PHOTOELECTRIC CONTROLS.....                      | 298 |
| 49-6.04.A | PHOTOELECTRIC UNIT.....                          | 298 |
| 49-6.04.B | CONTACTORS .....                                 | 299 |
| 49-6.04.C | CONTACTOR AND TEST SWITCH HOUSING.....           | 299 |
| 49-6.04.D | WIRING.....                                      | 299 |
| 49-7      | PROJECT-SUPPLIED EQUIPMENT .....                 | 299 |
| 49-8      | REMOVING AND SALVAGING ELECTRICAL EQUIPMENT..... | 299 |
| 49-9      | PAYMENT .....                                    | 299 |

## **SECTION 50 – CONSTRUCTION MATERIALS**

|          |   |     |
|----------|---|-----|
| 50-1     | PORTLAND CEMENT.....  | 301 |
| 50-2     | CONCRETE AGGREGATES.....  | 301 |
| 50-3     | WATER FOR CONCRETE.....   | 301 |
| 50-4     | PREMOULDED EXPANSION JOINT FILLER .....                                       | 301 |
| 50-5     | PORTLAND CEMENT CONCRETE.....   | 301 |
| 50-5.01  | COMPOSITION.....  | 301 |
| 50-5.02  | PROPORTIONING.....  | 302 |
| 50-5.03  | MIXING.....   | 302 |
| 50-5.04  | WATER CONTROL .....   | 303 |
| 50-6     | CURING COMPOUNDS FOR CONCRETE.....  | 304 |
| 50-7     | AGGREGATE BASES .....   | 304 |
| 50-8     | PIT RUN BASE (GRADED).....  | 304 |
| 50-9     | COBBLES .....   | 304 |
| 50-10    | GEOTEXTILE FABRIC.....  | 304 |
| 50-11    | CEMENT-TREATED BASES.....   | 305 |
| 50-12    | LIME TREATED BASE .....   | 305 |
| 50-13    | SAND .....  | 305 |
| 50-13.01 | RIVER SAND .....  | 305 |
| 50-13.02 | GRADED SAND .....   | 305 |
| 50-14    | CRUSHED ROCK.....   | 306 |
| 50-15    | CONTROL DENSITY BACKFILL.....   | 306 |
| 50-16    | CLEAN CRUSHED ROCK.....   | 308 |
| 50-17    | ASPHALT BINDERS AND EMULSION .....  | 308 |
| 50-18    | VITRIFIED CLAY PIPE (VCP) .....   | 308 |
| 50-19    | SUBSURFACE DRAINS .....   | 309 |
| 50-20    | NONREINFORCED CONCRETE PIPE (CP) .....  | 309 |
| 50-21    | REINFORCED CONCRETE PIPE, DRAINAGE (RCPD) .....                               | 309 |
| 50-22    | REINFORCED CONCRETE PIPE, SEWER (RCPS).....                                   | 309 |
| 50-23    | DUCTILE IRON PIPE (DIP), AND CAST IRON PIPE AND<br>DUCTILE IRON FITTINGS..... | 310 |
| 50-24    | POLYVINYL CHLORIDE (PVC) PIPE FOR SEWERS AND<br>DRAINAGE.....                 | 310 |
| 50-24.01 | PVC PIPE FOR DRAINAGE.....  | 310 |
| 50-25    | CORRUGATED STEEL PIPE (CSP) .....   | 311 |
| 50-26    | RIBBED STEEL PIPE (RSP).....  | 312 |
| 50-27    | CORRUGATED ALUMINUM PIPE (CAP).....   | 313 |

|                |   |     |
|----------------|---|-----|
| 50-28          | FIELD ASSEMBLED PLATE CULVERT .....               | 314 |
| 50-29          | HIGH DENSITY POLYETHYLENE PIPE (HDPE) .....       | 314 |
| 50-30          | REINFORCING STEEL, CURB DOWELS AND TIE BARS.....  | 316 |
| 50-31          | STORM DRAIN CASTINGS.....                         | 316 |
| 50-32          | JOINT MATERIALS FOR MANHOLES.....                 | 317 |
| 50-33          | FENCING - CHAIN LINK .....                        | 317 |
| 50-34          | LANDSCAPING MATERIALS.....                        | 319 |
| 50-34.01       | TOPSOIL .....                                     | 319 |
| 50-34.02       | COMMERCIAL FERTILIZER.....                        | 319 |
| 50-34.03       | SOIL AMENDMENT .....                              | 320 |
| 50-34.04       | IRON SULFATE .....                                | 320 |
| 50-34.05       | STRAW .....                                       | 320 |
| 50-34.06       | FIBER.....  | 320 |
| 50-34.07       | MULCH.....  | 320 |
| 50-34.08       | PLANTING MIX.....                                 | 321 |
| 50-34.09       | SEED .....  | 321 |
| 50-34.09.A     | TURF SEED.....                                    | 322 |
| 50-34.09.B     | WILDFLOWER SEED FOR HYDROSEEDING.....             | 322 |
| 50-34.10       | STABILIZING EMULSION .....                        | 322 |
| 50-34.11       | LUMBER.....                                       | 322 |
| 50-34.12       | TREE STAKES AND TIES.....                         | 322 |
| 50-34.13       | ROOT CONTROL BARRIER.....                         | 323 |
| 50-34.14       | PLANTS.....                                       | 323 |
| 50-34.14.A     | TURF.....   | 324 |
| 50-34.14.B     | TREES .....                                       | 324 |
| 50-34.15       | WATER.....  | 326 |
| 50-34.16       | IRRIGATION PIPE .....                             | 326 |
| 50-34.16.A     | STEEL PIPE .....                                  | 326 |
| 50-34.16.B     | PLASTIC PIPE.....                                 | 326 |
| 50-34.16.B.(1) | MAIN LINE.....                                    | 326 |
| 50-34.16.B.(2) | LATERAL LINE .....                                | 327 |
| 50-34.17       | SUBSURFACE DRIPPERLINE .....                      | 327 |
| 50-34.18       | IRRIGATION SLEEVING CONDUIT.....                  | 327 |
| 50-34.19       | SPRINKLERS AND EMITTERS.....                      | 328 |
| 50-34.20       | AUTOMATIC IRRIGATION CONTROLLERS.....             | 328 |
| 50-34.21       | QUICK COUPLING VALVES .....                       | 328 |
| 50-34.22       | CONTROL VALVES.....                               | 329 |
| 50-34.23       | MASTER CONTROL VALVE/FLOW SENSOR<br>ASSEMBLY..... | 329 |
| 50-34.24       | VALVE BOXES .....                                 | 329 |
| 50-34.25       | BACKFLOW PREVENTERS.....                          | 329 |
| 50-34.26       | CONCRETE .....                                    | 330 |
| 50-34.27       | FILTER ASSEMBLY UNITS.....                        | 330 |
| 50-34.28       | IPS FLEXIBLE PVC HOSE .....                       | 330 |
| 50-34.29       | GATE VALVES .....                                 | 330 |
| 50-34.30       | AIR VACUUM RELIEF VALVE .....                     | 331 |
| 50-34.31       | FLUSH VALVE ASSEMBLY .....                        | 331 |
| 50-34.32       | UNIONS.....                                       | 331 |
| 50-34.33       | IRRIGATION CONTROL WIRES .....                    | 331 |
| 50-34.34       | PULL BOXES .....                                  | 331 |
| 50-34.35       | PRESSURE GAUGES.....                              | 332 |
| 50-35          | ENGINEERING FABRICS .....                         | 332 |
| 50-36          | PAINT.....  | 332 |

|       |                                    |     |
|-------|------------------------------------|-----|
| 50-37 | LIQUID ASPHALT .....               | 332 |
| 50-38 | ASPHALTIC EMULSION.....            | 332 |
| 50-39 | EPOXY.....                         | 333 |
| 50-40 | PAVING STONES.....                 | 333 |
| 50-41 | COLORED OR PATTERNED CONCRETE..... | 334 |